ABBREVIATIONS LEGEND

NOTE 1: ABBREVIATIONS WHEN USED IN COMPOSITION MAY INCLUDE PERIODS FOR CLARIFICATION
NOTE 2: ABBREVIATIONS MAY BE DIFFERENT WHEN A PART OF A LEGEND

A/C	AIR CONDITION(ING)(ED)
ACC	ACCESSIBLE
ACST	ACOUSTIC(AL)
AD	AREA DRAIN
ADA	AMERICANS WITH DISABILITIES ACT
ADJ	ADJUSTABLE/ ADJACENT
AESS	ARCHITECTURALLY EXPOSED STRUCTURAL STEEL
AFC	ABOVE FINISHED COUNTER
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
AGGR	AGGREGATE
AHU	AIR HANDLING UNIT
ALT	ALTERNATE
ALUM	ALUMINUM
ANOD	ANODIZED(I)
APC	ACOUSTICAL PANEL CEILING
APPROX	APPROXIMATE
ARCH	ARCHITECT(URALLY), ARCHITECT
ASPH	ASPHALT
ATC	ACOUSTICAL TILE CEILING
AUTO	AUTOMATIC
AWT	ACOUSTICAL WALL TREATMENT
B/B	BACK TO BACK
BC	BACK OF CURB
BD	BOARD
BITUM	BITUMINOUS
BLDG	BUILDING
BM	BEAM/ BENCHMARK
BOT/	BOTTOM OF
BSMT	BASEMENT
BUR	BUILT-UP ROOFING
CAB	CABINET
CB	CATCH BASIN
CCTV	CLOSED CIRCUIT TELEVISION
CEM	CEMENT
CF/CI	CONTRACTOR FURNISHED, CONTRACTOR INSTALLED
CF/OI	CONTRACTOR FURNISHED, OWNER INSTALLED
CFM	CUBIC FEET PER MINUTE
CFMF	COLD-FORMED METAL FRAMING
CG	CORNER GUARD
CI	CAST IRON, CURB INLET
CIP	CAST-IN-PLACE
CJ	CONTROL JOINT
CL	CENTER LINE
CLG	CEILING
CLO	CLOSET
CLR	CLEAR
cm	CENTIMETER
CMU	CONCRETE MASONRY UNIT
CO	CLEANOUT
COL	COLUMN
CONC	CONCRETE
CONF	CONFERENCE
COORD	COORDINATE
CORR	CORRIDOR
CP	CARPET
CPT	CARPET TILES
CT	CERAMIC TILE
CTR	CENTER/CONTOUR
CU	CUBIC
CW	COLD WATER PIPING/ CHEMICAL WASTELINE
D	DEEP, DEPTH, PENNY (NAIL)
DBL	DOUBLE
DEG	DEGREE
DEMO	DEMOLISH, DEMOLITION
DEPT	DEPARTMENT
DF	DRINKING FOUNTAIN
DIA	DIAMETER (EXTERIOR)
DIAG	DIAGONAL
DIFF	DIFFUSER/ DIFFERENCE
DIM	DIMENSION
DISP	DISPENSER
DIV	DIVISION
DL	DEAD LOAD
DR	DOOR/ DRAIN
DS	DOWNSPOUT
DW	DISHWASHER
DWG	DRAWING
E	EAST
EA	EACH
EIFS	EXTERIOR INSULATION AND FINISH SYSTEM
EJ	EXPANSION JOINT
EL	ELEVATION
ELAST	ELASTOMERIC
ELEC	ELECTRIC(AL)
ELEV	ELEVATOR
EMER	EMERGENCY
EMER SHR	EMERGENCY SHOWER
ENGR	ENGINEER
ENTR	ENTRANCE
EO	ELECTRIC OUTLET
EOS	EDGE OF SLAB
EP	ELECTRICAL PANEL
EQ	EQUAL
EQUIP	EQUIPMENT
ETC	ET CETERA
EW	EACH WAY
EWC	ELECTRIC WATER COOLER
EXH	EXHAUST
EXIST	EXISTING
EXP	EXPANSION
EXT	EXTERIOR, EXTERNAL
F/F	FACE TO FACE
FCO	FLOOR CLEANOUT
FD	FLOOR DRAIN
FDC	FIRE DEPARTMENT CONNECTION
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER CABINET
FF	FINISH FACE
FH	FIRE HYDRANT
FHC	FIRE HOSE CABINET
FIN	FINISH(ED)
FF EL	FINISHED FLOOR ELEVATION
FLR	FLOOR
FLUOR	FLUORESCENT
FO	FINISHED OPENING
FOC	FACE OF CURB
FOF	FACE OF FINISH
FOM	FACE OF MASONRY
FOS	FACE OF SLAB/ FACE OF STUD
FP	FIRE PROTECTION/ FIREPROOF
FRTW	FIRE RETARDANT TREATED WOOD
FT	FOOT (FEET)/ FIRE TREATED
FTG	FOOTING
FURG	FURRING
FURN	FURNISH, FURNITURE
FUT	FUTURE
FV	FIELD VERIFY
GA	GAGE
GALV	GALVANIZED
GEN	GENERAL
GFRC	GLASS FIBER REINFORCED CONCRETE
GFRG	GLASS FIBER REINFORCED GYPSUM
GL	GLASS
GL BLK	GLASS BLOCK
GLU LAM	GLUED LAMINATED WOOD
GR LN	GRADE LINE
GRFL	GROUND FLOOR
GSB	GYPSUM SHEATHING BOARD
GT	GREASE TRAP
GYP BD	GYPSUM BOARD
GYP PLAS	GYPSUM PLASTER
H	HIGH
HB	HOSE BIBB
HC	HOLLOW CORE
HDW	HARDWARE
HDWD	HARDWOOD
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HPT	HIGH POINT
HSKPG	HOUSEKEEPING
HT	HEIGHT
HVAC	HEATING, VENTILATION, AIR CONDITIONING
HW	HOT WATER
ID	INSIDE DIAMETER
INCAND	INCANDESCENT
INSUL	INSULATION
INT	INTERIOR
INV	INVERT
JAN CLO	JANITOR'S CLOSET
KIT	KITCHEN
L	LONG, LENGTH
LAM	LAMINATE(D)
LAU	LAUNDRY
LAV	LAVATORY
LB(S)	POUND(S)
LF	LINEAR FOOT, (FEET)
LH	LEFT HAND
LIB	LIBRARY
LKR	LOCKER
LL	LIVE LOAD
LONG	LONGITUDINAL
LOC	LOCATION
LPT	LOW POINT
LT	LIGHT
LVR	LOUVER
m	METER
MACH	MACHINE
MAINT	MAINTENANCE
MATL	MATERIAL
MAX	MAXIMUM
MECH	MECHANICAL
MEMB	MEMBRANE
MEP	MECHANICAL, ELECTRICAL, PLUMBING, FIRE PROTECTION
MEZZ	MEZZANINE
MFR	MANUFACTURER
MH	MANHOLE
MHO	MAGNETIC HOLD OPEN
MIN	MINIMUM
MISC	MISCELLANEOUS
MKR BD	MARKER BOARD
mm	MILLIMETER
MO	MASONRY OPENING
MTL	METAL
N	NORTH
NIC	NOT IN CONTRACT
NO	NUMBER
NOM	NOMINAL
NTS	NOT TO SCALE
O/O	OUT TO OUT
OC	ON CENTER
OD	OUTSIDE DIAMETER
OF/CI	OWNER FURNISHED, CONTRACTOR INSTALLED
OF/OI	OWNER FURNISHED, OWNER INSTALLED
OFF	OFFICE
OPH	OPPOSITE HAND
OPNG	OPENING
OPP	OPPOSITE
ORD	OVERFLOW ROOF DRAIN
PA	PUBLIC ADDRESS
PAR	PARAPET, PARALLEL
PCC	PRE-CAST CONCRETE
PERF	PERFORATED
PERP	PERPENDICULAR
PLAM	PLASTIC LAMINATE
PLAS	PLASTER
PLBG	PLUMBING
PLYWD	PLYWOOD
PMD1	PARK MAINTENANCE DISTRICT 1
PNT	PAINT
POL	POLISHED
PR	PAIR
PREFAB	PREFABRICATE(D)
PROJ	PROJECT
PROP	PROPERTY
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	POINT/ PRESSURE TREATED
PTD	PAPER TOWEL DISPENSER
PTN	PARTITION
PVC	POLYVINYL CHLORIDE
PVG	PAVING
QT	QUARRY TILE
QTY	QUANTITY
R	THERMAL RESISTANCE, RADIUS, RISER
RB	RUBBER BASE
RC	REINFORCED CONCRETE
RCP	REFLECTED CEILING PLAN
RCPTN	RECEPTION
RD	ROOF DRAIN
REC	RECESSED
REF	REFERENCE, REFRIGERATOR
REINF	REINFORCE, REINFORCING
REQ(D)	REQUIRE, REQUIRED
RESIL	RESILIENT
REV	REVISION
RF	RESILIENT FLOORING
RH	RIGHT HAND
RM	ROOM
RO	ROUGH OPENING
ROW	RIGHT-OF-WAY
RTF	RUBBER TILE FLOOR
RVL	REVEAL
S	SOUTH
SAN	SANITARY
SC	SOLID CORE
SCHED	SCHEDULE
SECT	SECTION
SF	SQUARE FOOT(FEET)
SGL	SINGLE
SHR	SHOWER
SHT	SHEET
SIM	SIMILAR
SJ	SLIP JOINT, SCORED JOINT
SPEC	SPECIFICATION
SPKR	SPEAKER
SQ	SQUARE
SST	STAINLESS STEEL
STA	STATION
STC	SOUND TRANSMISSION CLASS
STD	STANDARD
STL	STEEL
STOR	STORAGE
STRUCT	STRUCTURAL
SUSP	SUSPENDED
SV	SHEET VINYL
SYMM	SYMMETRICAL
T	TREAD
T/	TOP OF
TA	TOILET ACCESSORY
T&B	TOP & BOTTOM
T&G	TONGUE & GROOVE
TEL	TELEPHONE
TEMP	TEMPORARY
TER	TERRAZZO
THK	THICK
TI	TENANT IMPROVEMENT
TO_	TOP OF _____
TOPO	TOPOGRAPHY, TOPOGRAPHIC
TRTD	TREATED
TS	TUBE STEEL
TV	TELEVISION
TYP	TYPICAL
U	HEAT TRANSFER COEFFICIENT
UH	UNIT HEATER
UL	UNDERWRITER'S LABORATORIES
UNEX	UNEXCAVATED
UNFIN	UNFINISHED
UNO	UNLESS NOTED OTHERWISE
UTIL	UTILITY
VB	VINYL BASE
VCT	VINYL COMPOSITION TILE
VENT	VENTILATION
VERT	VERTICAL
VEST	VESTIBULE
VIF	VERIFY IN FIELD
VNR	VENEER
VOL	VOLUME
VWC	VINYL WALL COVERING
W	WEST
W/	WITH
W/O	WITHOUT
WC	WATER CLOSET
WD	WOOD
WG	WALL GUARD
WH	WATER HEATER
WI	WROUGHT IRON
WSCT	WAINSCOT
WT	WEIGHT
WWF	WELDED WIRE FABRIC
WWM	WELDED WIRE MESH
X	BY
YD	YARD
YR	YEAR
ZN	ZINC

SYMBOLS

&	AND
@	ANGLE
∡	AT
℄	BY (LOWERCASE)
℄	CENTER LINE
[	CHANNEL
X°	DEGREE
Ø	DIAMETER
∠	DOUBLE ANGLE
#	NUMBER, POUNDS
₹	PROPERTY LINE
±	PLUS OR MINUS
▫	SQUARE FEET
⌐	ZEE
□	COLUMN; TUBE
/	DIVIDED BY

MATERIALS

- COMPACTED FILL EARTH WORK
- UNDISTURBED SOIL
- GRAVEL, POROUS FILL
- SAND
- ASPHALT
- STRUCTURAL CONCRETE
- LIGHTWEIGHT CONCRETE
- BRICK, COMMON FACE
- CONCRETE MASONRY UNIT
- STEEL
- ALUMINUM
- ORNAMENTAL METAL
- CONTINUOUS WOOD FRAMING
- BLOCKING OR SHIM
- FINISH WOODWORK
- PLYWOOD
- PARTICLE BOARD
- GYPSUM WALLBOARD
- WATERPROOFING/ DAMPROOFING/ AIR/ MOISTURE BARRIER
- RIGID INSULATION
- BATT INSULATION
- CARPETING (LARGE SCALE)
- RESILIENT FLOORING
- GLASS
- ACOUSTICAL CEILING BOARD
- SPRAY-ON FIREPROOFING
- EXTERIOR SHEATHING
- SOLID SURFACING
- PLASTER STUCCO W/ METAL LATH

SYMBOLS LEGEND

COLUMN GRID DESIGNATION



NEW GRID



EXISTING GRID

NOTE TAGS

"NOTES BY NUMBER"

SPECIFICATION KEYNOTES

BUILDING SECTION TAG



SECTION DESIGNATION

SHEET NUMBER

WALL / DETAIL SECTION TAGS



SECTION DESIGNATION

SHEET NUMBER

SIM

SIMILAR DETAIL DESIGNATION

DETAIL DESIGNATION

SHEET NUMBER

ENLARGED PLAN TAG



PLAN OR DETAIL DESIGNATION

SHEET NUMBER

EXTERIOR ELEVATION TAG

ELEVATION DESIGNATION

SHEET NUMBER

INTERIOR ELEVATION TAG



SINGLE INTERIOR ELEVATION TAG

DESIGNATION SHEET #

ELEVATION DESIGNATION (TYP.)

SHEET NUMBER

DOOR IDENTIFICATION TAG

DOOR DESIGNATOR

ROOM NUMBER (THAT DOOR SWINGS INTO)

EQUIPMENT DESIGNATION



OWNER FURNISHED EQUIPMENT / ITEM REF OWNER EQUIPMENT MANUAL

OWNER FURNISHED EQUIPMENT/ ITEM

CONTRACTOR FURNISHED EQUIPMENT/ ITEM

TOILET ACCESSORY TAG

WINDOW TYPE SYMBOL

INTERIOR GLAZING SYSTEM TAG (NUMERIC)

EXTERIOR GLAZING SYSTEM TAG (ALPHA)

LOUVER TYPE IDENTIFIER (ALPHA AND NUMERIC)

PARTITION TAG



PARTITION TYPE

FLOOR DRAIN

ROOF DRAIN AND OVERFLOW DRAIN



OVERFLOW DRAIN

ROOF DRAIN

GLAZING TAG

GLAZING DESIGNATION

ARCHITECTURAL WOODWORK



NO BOX INDICATES ARCHITECTURAL WOODWORK REF A-541 FOR ARCHITECTURAL WOODWORK SECTIONS AND DETAILS

EXISTING PARTITION / ITEM TO REMAIN

NEW PARTITION / ITEM

EXISTING TO BE REMOVED

OUT OF SCOPE AREA

GENERAL PROJECT NOTES

1. REFER TO COMPLETE SET OF ISSUED CONTRACT DOCUMENTS FOR APPLICABLE NOTES, ABBREVIATIONS, AND SYMBOLS.
2. DO NOT SCALE THE DRAWING. IF DIMENSIONS ARE IN QUESTION, OBTAIN CLARIFICATION FROM THE ARCHITECT BEFORE CONTINUING.
3. DIMENSIONS SHOWN ON THE FLOOR PLANS FOR NEW CONSTRUCTION ARE TO THE FACE OF FINISH OF INTERIOR WALLS, TO CENTER LINE OF COLUMNS AND TO FACE OF CONCRETE OR MASONRY WALLS, UNLESS OTHERWISE INDICATED. DIMENSIONS IN RENOVATED AREAS ARE FROM FINISH FACE OF EXISTING WALLS AND TO FINISH FACE OF NEW STUD WALLS, UNLESS OTHERWISE INDICATED.
4. FIELD MEASURE AND CONFIRM DIMENSIONS FOR OWNER PROVIDED EQUIPMENT AND FURNISHINGS. COORDINATE WITH THE OWNER ON DELIVERY AND INSTALLATION OF OF/CI EQUIPMENT. MINIMUM REQUIRED OPENINGS AND ACCESSIBLE ROUTES TO THE INSTALLATION AREA SHALL BE COORDINATED WITH THE SUPPLIER.
5. FINISH FLOOR ELEVATIONS ARE TO TOP OF CONCRETE SLAB UNLESS OTHERWISE NOTED.
6. COORDINATE EXACT SIZE AND PLACEMENT OF EQUIPMENT BASE AND HOUSEKEEPING PADS WITH EQUIPMENT TO BE PROVIDED.
7. WHERE NEW GYPSUM BOARD PARTITIONS ARE A CONTINUATION OF AN EXISTING PARTITION OR COLUMN ENCASEMENT, THE FACE OF THE NEW GYPSUM BOARD SHALL BE ALIGNED WITH THE FACE OF THE EXISTING SURFACE. WHERE A ONE HOUR PARTITION IS SHOWN AS A CONTINUATION OF A TWO-HOUR PARTITION OR COLUMN ENCASEMENT, THE FACE OF THE GYPSUM BOARD SHALL BE OFFSET AS REQUIRED TO PROVIDE FACE ALIGNMENT OF GYPSUM BOARD ON BOTHSIDES.
8. LEVEL FLOORS SO THAT THEY DO NOT EXCEED A ½" VARIANCE IN A 10'-0" RADIUS IN ALL DIRECTIONS.
9. PIPING LOCATED ABOVE GRADE AND INSIDE THE BUILDING SHALL BE CONCEALED IN FURRED SPACES WITH THE EXCEPTION OF PIPING IN STAIRWAYS, EQUIPMENT ROOMS AND POWERHOUSE. COORDINATE WITH OTHER TRADES TO PROVIDE FURRING FOR PIPING INSTALLED IN FINISHED AREAS.
10. ALL EXTERIOR STEEL HANDRAILS, GUARDRAILS, AND BOLLARDS SHALL BE GALVANIZED AND PAINTED UNLESS OTHERWISE NOTED.
11. PARTITION TYPES AND FIRE RESISTIVE RATINGS INDICATED ON A WALL ARE TO BE CONTINUOUS FOR THE LENGTH AND HEIGHT OF A PARTITION.
12. APPROVE FLOOR OUTLET LOCATIONS WITH ARCHITECT AND BUILDING MANAGEMENT PRIOR TO CORE DRILLING.
13. OPENINGS IN A RATED WALL, FLOOR, CEILING AND ROOF ASSEMBLIES SHALL BE SEALED WITH A FIRE RESISTANT JOINT SYSTEMS OR PROTECTED WITH A FIRE RATED CHASE.
14. EXIT SIGNS AND SMOKE DETECTORS LOCATED IN CEILINGS SHALL BE POSITIONED AS REQUIRED BY THE AUTHORITY HAVING JURISDICTION.
15. WHERE MATERIALS ARE APPLIED TO, OR ARE IN DIRECT CONTACT WITH WORK INSTALLED BY ANOTHER SUBCONTRACTOR, COMMENCEMENT OF WORK IMPLIES ACCEPTANCE OF THE SUBSTRATE AS SUITABLE FOR THE APPLICATION INTENDED.
16. ISOLATE DISSIMILAR METALS TO PREVENT GALVANIC CORROSION.
17. SEALANTS EXPOSED TO VIEW SHALL BE CUSTOM COLOR AS SELECTED BY THE ARCHITECT.
18. COORDINATE LOCATION OF SEALANT AND COMPATIBILITY OF SEALANTS WITH ADJACENT WORK, INCLUDING MATERIALS AND OTHER CONTIGUOUS SEALANTS.
19. CAULK AT JUNCTURE OF INTERIOR FACES OF DOOR FRAMES, VIEW WINDOW FRAMES, EXTERIOR WINDOW FRAMES, AND CABINET WORK WITH ADJACENT MATERIALS. MAINTAIN THE FIRE RATING OF CONSTRUCTION. AROUND CABINETS, PANELS, AND BOXES RECESSED IN FIRE RATED WALL, FLOOR, AND CEILING ASSEMBLIES.
20. ACCESSORIES SUCH AS GRAB BARS, TOWEL BARS, PAPER DISPENSERS AND SOAP DISHES INSTALLED WITHIN 2' OF A URINAL, WATER CLOSET, SINK OR LAVATORY SHALL BE MOISTURE SEALED.
21. DO NOT HANG (SUPPORT) ANY ITEMS FROM METAL ROOF DECK. IT IS ACCEPTABLE TO ATTACH, I.E. CEILING SYSTEM WIRE HANGERS FROM JOISTS AND/ OR BEAMS. IF NO JOIST OR BEAM, PROVIDE A STEEL STRIP.

PERKINS + WILL

10100 North Central Expressway
Suite 300
Dallas, Texas 75231
t 214.283.8700
f 214.283.8701
www.perkinswill.com

DALLAS PARK AND RECREATION DEPARTMENT ADMINISTRATIVE OFFICES

10031 E. NORTHWEST HWY
DALLAS, TX 75238

LANDSCAPE
KEVIN SLOAN STUDIO
2400 EMPIRE CENTRAL, SUITE F
DALLAS, TX 75235
MATT STUBBS
(214) 459-1784

STRUCTURAL
RLG ENGINEERING
5445 La Sierra SUITE 300
DALLAS, TX 75231
ANDY AAYERS
214.739.8100

MEP
SW ASSOCIATES
5429 LBJ FWY
SUITE 300 - LB129
DALLAS, TX 75240
CARL HEWETT
214.397.0211

REGISTERED ARCHITECT — KEVIN LYNN CALLAHAN — STATE OF TEXAS

08/25/16

Revisions

NO	ISSUE	DATE

Sheet Information

Date	AUGUST 25, 2016
Job Number	146054.000
Drawn	VBW
Checked	RC
Approved	PLC

Title

ARCHITECTURAL ABBREVIATIONS, SYMBOLS & GEN NOTES

Sheet

A-001

Copyright © 2013 Perkins+Will

8/25/2016 9:22:45 AM
\\perkinswill.net\Projects\Dallas\146054.000.JE Muchert SA1\DESIGN\BIM\REVIT\ARCH_JE\M_2.rvt